

MATERIAL SCHEDULE (BOTH CELLS)

PART #	QTY REQ'D	QTY TO SHIP	MAT 'L	DESCRIPTION
LAXF11	46	46	FRP	4" x 1 1/8" x 1/4" x 3'-3" LOUVER ARM
LAXF12	46	46	FRP	4" x 1 1/8" x 1/4" x 3'-11 7/8" LOUVER ARM
LAXF13	368	368	FRP	4" x 1 1/8" x 1/4" x 3'-11 7/8" LOUVER ARM
PLA	460	460	PLA	MWT PLASTIC LOUVER ARM


HARDWARE SCHEDULE

PART #	QTY REQ'D	QTY TO SHIP	MAT 'L	DESCRIPTION
-	460	480	316 SS	1/4" x 4 1/2" BOLT (W/ 1 NYLON INSERT LOCKNUT, 2 FLAT WASHERS, 1 LOCK WASHERS)
-	460	480	316 SS	3/8" x 5" BOLT (W/ 1 NYLON INSERT LOCKNUT, 2 FLAT WASHERS, 1 LOCK WASHERS)
-	46	50	316 SS	1/2" x 2 1/2" TFL BOLT (W/ 1 NYLON INSERT LOCKNUT, 2 FLAT WASHERS, 1 LOCK WASHERS)
-	414	440	316 SS	1/2" x 6" BOLT (3" THREAD) (W/ 1 NYLON INSERT LOCKNUT, 2 FLAT WASHERS, 1 LOCK WASHERS)
-	2930	3100	316 SS	#12 x 1 1/2" HEX HEAD SELF DRILLING SCREW w/ NEOPRENE WASHER
-	60	60	*	VULKEM CAULK TUBE

THIS SECTION IS FOR DRAFTING DEPARTMENT REFERENCE ONLY	0	# TRANSVERSE LOUVER ROWS	9	# LONGITUDINAL BENTLINES
	14	# LONGITUDINAL LOUVER ROWS	73	# TRANSVERSE BENTLINES
	42'	INLET HEIGHT		

TRANSVERSE VIEW

REVISIONS				
DATE	DESCRIPTION	BY	CHECK	
2-29-2016	INITIAL ISSUE			



STAR COOLING TOWERS LP

9007 FM 2759 RICHMOND, TX 77469 PH. 713 645-3323 FAX 713 645-3029
 1000 W. MCNAB RD, SUITE 236 POMPANO BEACH, FL 33062 PH. 954 532-0177 FAX 954 532-0351

PROJECT:		
LOCATION:		
DRAWING TITLE: INLET LOUVER INSTALLATION & DETAILS		
PROJECT NO. 160325	DRAWN BY: RC	CHECKED BY: TTH
DWG. # B510	Scale: NONE	SHEET: 1 OF 1